



भाकृअनुप - केन्द्रीय बाराणी कृषि अनुसन्धान संस्थान

ICAR - Central Research Institute for Dryland Agriculture

संतोषनगर, सैदाबाद-पोस्ट हैदराबाद ५०००५९ Santoshnagar, Saidabad P.O. Hyderabad 500 059
040-24530161,24530163,2Fax:040-24531802 www.icar-crida.res.in Email : hoa.crida@icar.gov.in



e-F.No: 4-7/(50)/2023-24/CDN
Date:12.12.2023

Sub: Quotations for **Repair works/Petty works/Erection of Selfie Point at ICAR-CRIDA** – reg.

Dear Sir(s),

Quotations are invited for following Repair/Works as detailed below:

SL NO	NAME OF THE WORK	PARTICULAR
1	RENOVATION OF ACADEMIC STAFF ROOMS & CLASS ROOMS IN MAIN BUILDING	AS PER ENCLOSED SPECIFICATION WORK 1
2	REPAIRS, REPLACEMENT OF WINDOW PANES GATE AND DEEP CLEANING OF KITCHEN AND DINNING HALL IN TTC HOSTEL	AS PER ENCLOSED SPECIFICATION WORK 2
3	RENOVATION ,REPLACEMENT OF DAMAGED SANITARY FIXTURES AND WHITE WASHING OF ROOMS IN TTC HOSTEL	AS PER ENCLOSED SPECIFICATION WORK 3
4	SELFIE POINT INDICATING SALIENT ACHIEVEMENTS OF THE INSTITUTES	AS PER ENCLOSED SPECIFICATION WORK 4
5	REPAIR AND PAINTING OF ROOM IN GRF.	AS PER ENCLOSED SPECIFICATION WORK 5
6	CONSTRUCTION OF BAMBOO SHED AT HRF	AS PER ENCLOSED SPECIFICATION WORK 6

TERMS & CONDITIONS

- The last date for submission of quotation is **02.01.2024**. Rates offered shall be F.O.R. CRIDA, Hyderabad
- The work shall be carried out as per this Institute Specification and as per the directions of Institute Chairman, IWMC or and Indenting officer and the payment will be made after satisfactory completion of work duly certified by the Indenting Officer
- Quotations should be submitted in a sealed cover addressed to the Director, Central Research Institute for Dryland Agriculture, Santoshnagar, Saidabad Post, Hyderabad – 500 059. The cover containing quotation should invariably be super scribed.
 - Due on 02.01.2024 17.00 hrs**
 - For supply of material for repairs / masonry / Digging / plastering works etc.
- The quotation should remain valid for a period of 90 days from the date (due date)
- No advance payment/delivery against payment is permissible. However, the payment shall be arranged in 15 days from the date of submission of pre-receipted bill in triplicate along with stores.
- The rates quoted should be net payable for each item/material for delivery at the Institute at the address given above (inclusive of all taxes-GST, packing, forwarding, transport, insurance and excluding rebate/discount etc.)
- While quoting the rates please mention the following:
 - Approximate time for supply of material from the date of placing order.
 - Guarantee/Warranty/Expiry period
 - Any other condition
- The participating bidder must submit a copy of GST and PAN card
- Time allowed for completion of the work 30 days
- Quotation which do not conform to the above terms and conditions will not be considered. The Director, Central Research Institute for Dryland Agriculture, reserves the right to accept or reject any or all quotations without assigning any reasons thereof.

Yours faithfully

Assistant Administrative Officer (CDN)

WORK 1: RENOVATION OF ACADEMIC STAFF ROOMS & CLASS ROOMS IN MAIN BUILDING

SI no	DSR item no	Description	Nos	QTY	Units	Unit Rate	Amount
1.	DSR no : 13.39.1	Colour washing such as green, blue or buff to give an even shade : New work (two or more coats) with a base coat of white washing with lime .	1	720	Sqm		
2.	DSR no:13.87.1	Ceiling for White washing with lime to give an even shade :Old work (two or more coats) .	1	260	sqm		
3.	DSR no:13.53.1	Painting on G.S. sheet with synthetic enamel paint of approved brand and manufacture of required colour to give an even shade New work (two or more coats) including a coat of approved steel primer but excluding a coat of mordant solution	1	75.33	Sqm		
4.	DSR no:13.104.1	Polishing on wood work with ready made wax polish of approved brand and manufacture : Old work	1	116.54	Sqm		
5.	DSR no:14.5.1	Renewing glass panes, with putty and nails wherever necessary including racking out the old putty: Float glass panes of nominal thickness 4 mm (weight not less than 10kg/sqm)	1	13.68	Sqm		
6.	DSR no:13.80	Providing and applying white cement based putty of average thickness 1 mm, of approved brand and manufacturer, over the plastered wall surface to prepare the surface even and smooth complete.	1	64	sqm		
7.	MR	Wooden 4 mm Laminate decolam sheet	1	6	nos		
8.	MR	Wooden Beading	1	70	RM		
9.	MR	Skilled Carpenter	1	4	nos		
10.	DSR-17.2.1	Providing and fixing white vitreous china pedestal type water closet(European type W.C. pan) with seat and lid, 10 litre low level white P.V.C. flushing cistern, including flush pipe, with manually controlled device (handle lever), conforming to IS : 7231, with all fittings and fixtures complete, including cutting and making good the walls and floors wherever required :W.C. pan with ISI marked white solid plastic seat and lid.	1	1	nos		
11.	DSR-17.71	Providing and fixing PTMT liquid soap container 109 mm wide, 125mm high and 112 mm distance from wall of standard shape with bracket of the same materials with snap fittings of approved quality and colour, weighing not less than 105 gms.	1	2	each		
12.	MR	Branded make BAT Full Brass 2 in one tap Two Way tap for Bathroom 2 in 1 tap for Washing Machine 2 in 1 tap for Bathroom	1	2	each		

		with Wall Flange and Teflon Tape (Chrome Finish)					
13.	MR	AC units repairs and services	1	LS	nos		
14.	MR	Electrical miscellaneous items	1	LS	nos		
15.	MR	Deep cleaning	4	4	nos		
16.		Total cost					
17.		GST					
18.		Contingencies if any					
19.		Total amount					

WORK 2: REPAIRS, REPLACEMENT OF WINDOW PANES GATE AND DEEP CLEANING OF KITCHEN AND DINNING HALL IN TTC HOSTEL

SI no	DSR item no	Description	Nos	QTY	Units	Unit Rate	Amount
1	MR	Cement concrete flooring 1:2:4 (1 cement : 2 coarse sand : 4 graded stone aggregate) finished with a floating coat of neat cement, including cement slurry, but excluding the cost of nosing of steps etc. complete. 40 mm thick with 20 mm nominal size stone aggregate	40	sqm	545		
2	MR	UPVC Plastic Plumbing Pipes, Size/Diameter: 1/2 Inch, 1 Inch, 2 Inch, 3 Inch	60	Rm	78		
3	DSR - 7257	C.P. Brass bibcock 15 mm	10	each	300		
4	DSR - 15.9.2	Demolishing stone rubble masonry manually/ by mechanical means including stacking of serviceable material and disposal of unserviceable material within 50 metres lead as per direction of Engineer-in-charge : In cement mortar cum 2027.10	3	cum	2027.1		
5	DSR :14.5.1	Renewing glass panes, with putty and nails wherever necessary including racking out the old putty: Float glass panes of nominal thickness 4 mm (weight not less than 10kg/sqm)	21	sqm	941.95		
6	MR	Powder Coating Three Track Aluminium Sliding Window, Size/Dimension: 4 X 6 Ft	76.4 4	Sft	260		
7	DSR :13.53.1	Painting on G.S. sheet with synthetic enamel paint of approved brand and manufacture of required colour to give an even shade New work (two or more coats) including a coat of approved steel primer but excluding a coat of mordant solution	15	Sqm	150.2		
8	DSR :10.3	Providing and fixing in position collapsible steel shutters with vertical channels 20x10x2 mm and braced with flat iron diagonals 20x5 mm size, with top and bottom rail of T-iron 40x40x6 mm, with 40 mm dia steel pulleys, complete with bolts, nuts, locking arrangement, stoppers, handles, including applying a priming coat of approved steel primer. sqm 9397.35	6.6	sqm	9397.3 5		
9	MR	Deep Cleaning of wash rooms and dinning hall and kitchen room as per E.I.c		LS	10000		
10		Total cost					
11		GST					
12		Contingencies if any					
13		Total amount					

WORK 3: RENOVATION ,REPLACEMENT OF DAMAGED SANITARY FIXTURES AND WHITE WASHING OF ROOMS IN TTC HOSTEL

SI no	DSR item no	Description	Nos	QTY	Units	Unit Rate	Amount
1	DSR-17.2.1	Providing and fixing white vitreous china pedestal type water closet(European type W.C. pan) with seat and lid, 10 litre low level whiteP.V.C. flushing cistern, including flush pipe, with manually controlleddevice (handle lever), conforming to IS : 7231, with all fittings andfixtures complete, including cutting and making good the walls andfloors wherever required :W.C. pan with ISI marked white solid plastic seat and lid.	5	each	5540.55		
2	DSR-17.16A	Providing and fixing 8 mm dia C.P. / S.S. Jet with flexible tube upto1 metre long with S.S. triangular plate to European type W.C. ofquality and make as approved by Engineer - in - charge.	17	each	299.3		
3	DSR-17.32.2	Providing and fixing mirror of superior glass (of approved quality) and of required shape and size with plastic moulded frame of approved make and shade with 6 mm thick hard board backing : Rectangular shape 453x357 mm	11	each	1158.95		
4	DSR-1369	S.C.I. gully or nahani grating 100 mm dia .	20	each	25		
5	DSR-17.73.1	Providing and fixing PTMT towel rail complete with brackets fixed towooden cleats with CP brass screws with concealed fittingsarrangement of approved quality and colour.450 mm long towel rail with total length of 495 mm78 mm wide and effective height of 88 mm, weighing notless than 170 gms.	30	each	573.6		
6	DSR-17.71	Providing and fixing PTMT liquid soap container 109 mm wide, 125mm high and 112 mm distance from wall of standard shape withbracket of the same materials with snap fittings of approved qualityand colour, weighing not less than 105 gms.	40	each	146.3		
7	DSR-7073	Adjustable Vitreous China Cistern with fittings of flushing capacity3 litre/ 6litre 9adjustibla to 4 litre/8litre)	20	each	1600		
8	DSR - 7257	C.P. Brass bibcock 15 mm	70	each	300		
9	DSR-18.22.1	Providing and fixing C.P. brass shower rose with 15 or 20 mm inlet : 100 mm diameter .	30	each	166.35		
10	DSR-8664	Aluminium round shape handle (powder coated) outer dia 100 mm	150	each	60		
11	DSR-17.28.2.1	Providing and fixing P.V.C. waste pipe for sink or wash basin including P.V.C. waste fittings complete. Flexible pipe 32 mm dia.	100	each	104.35		
12	DSR-14.5.2	Renewing glass panes, with putty and nails wherever necessary including racking out the old putty: Float glass panes of nominal thickness 5 mm (weight not less than 12.5kg/sqm)	25	sqm	1245.15		
13	DSR - 13.87.1	White washing with lime to give an even shade :Old work (two or more coats) .	2182	sqm	19		
14	DSR :13.80	Providing and applying white cement based putty of average thickness 1 mm, of approved brand and manufacturer, over the plastered wall surface to prepare the surface even and smooth complete.	405	sqm	123.85		

15	DSR :13.104.1	Polishing on wood work with ready made wax polish of approved brand and manufacture : Old work	100.8	sqm	82.95		
16	DSR :13.61.1	Painting with synthetic enamel paint of approved brand and manufacture to give an even shade : Two or more coats on new work	130	sqm	131.45		
17	MR	Wooden 4 mm Laminate decolam sheet	9	each	1000		
18	MR	Wooden Beading	120	RM	22		
19	MR	Skilled Carpenter	4	nos	1200		
20	MR	Deep Cleaning of wash rooms		LS	20000		
21		Total cost					
22		GST					
23		Contingencies if any					
24		Total Amount					

WORK 4: SELFIE POINT INDICATING SALIENT ACHIEVEMENTS OF THE INSTITUTES

Sl no	Description	Amount Quoted
1	<p>Selfie Point Specifications</p> <p>Base plat form including foundation -- 90 X 18 cm size & 600 cm length.</p> <p>Signage fixing support frame -- MS 75 x 75 mm heavy duty pipe and flats coated with anti-rust primer</p> <p>Signage make – 2mm thick SS back and imported 3mm Acrylic sheet on front -- 9 letters of 76.2 cm size (include 2 Logos) ;</p> <p>LED Lights – High bright, Reputed brad, 2 Watts, with proper wiring and 5 Years warranty.</p> <p>Proper size cable box with plug and ply fitting and drives.</p>	
	Total cost	
	GST	
	Contingencies if any	
	Total Amount	

WORK 5: REPAIR AND PAINTING OF ROOM IN GRF.

Sl.No	DSR item no	Description	QTY	Unit Rate, Rs	Unit	Amount, Rs
1	DSR no:14.1.1	Repairs to plaster of thickness 12 mm to 20 mm in patches of area 2.5 sq.meters and under, including cutting the patch in proper shape, raking out joints and preparing and plastering the surface of the walls complete, including disposal of rubbish to the dumping ground, all complete as per direction of Engineer-in-Charge. With cement mortar 1:4 (1 cement : 4 fine sand)	12		sqm	

2	DSR no:14.10	Refixing old glass panes with putty and nails	3		sqm	
3	DSR no:13.88	Removing white or colour wash by scrapping and sand papering and preparing the surface smooth including necessary repairs to scratches etc.	150.49		sqm	
4	DSR no:13.26	Providing and applying plaster of paris putty of 2 mm thickness over plastered surface to prepare the surface even and smooth complete.	71.74		sqm	
5	DSR no:13.62.1	Painting with synthetic enamel paint of approved brand and manufacture of required colour to give an even shade : Two or more coats on new work over an under coat of suitable shade with ordinary paint of approved brand and manufacture.	170		sqm	
6	DSR no:13.111.1	Finishing walls with Acrylic Smooth exterior paint of required shade :Old work (Two or more coat applied @ 1.67 ltr/ 10 sqm) on existing cement paint surface.	70.5		sqm	
7	DSR no:13.61.1	Painting with synthetic enamel paint of approved brand and manufacture to give an even shade : Two or more coats on new work	15		sqm	
8	DSR no:15.23.1	Dismantling tile work in floors and roofs laid in cement mortar including stacking material within 50 metres lead. For thickness of tiles 10 mm to 25 mm .	36		sqm	
9	DSR no:11.41.2	Providing and laying vitrified floor tiles in different sizes (thickness to be specified by the manufacturer) with water absorption less than 0.08% and conforming to IS: 15622, of approved make, in all colours and shades, laid on 20mm thick cement mortar 1:4 (1 cement: 4 coarse sand), jointing with grey cement slurry @ 3.3 kg/ sqm including grouting the joints with white cement and matching pigments etc., complete. Size of Tile 600x600 mm .	32.95		sqm	
10	MR	Miscellaneous items			LS	
		Total Cost				
		GST				
		Contingency if any				
		Total Amount				

WORK 6: CONSTRUCTION OF BAMBOO SHED

S.No	Description of Item	Amount (Rs.) incl. GST
1	Reinforced Cement Concrete pillars (9 X 9 Inches size, 8Nos of 7 feet length include 3feet above ground (1:1.5:3 ratio Cement , course sand and 20mm gravel metal) with 6 Nos 12mm dia steel frame work	
2	Reinforced Cement Concrete rectangular frame (20 X 15 Feet size). Frame (9 X 9 Inches size) composed of 1:1.5:3 ratio Cement , course sand and 20mm gravel metal with 6 Nos 12mm dia steel frame work (2 nos 16 mm steel rods at bottom)	
3	Provision of mild steel Piller posts (10 to 12 Feet each – 8 Nos, 3inch outer dia and 3mm wall thickness) and Base plates for posts(10mm thick) Nuts and bolts 8 x 6 Nos = 48 Nos)	
Total cost Rs. _____		
Total cost Quoted in words:		